


LAKE BLUFFS DRAIN LEELANAU COUNTY DRAIN COMISSIONER

SECTION 14, TOWN 28 NORTH, RANGE 12 WEST, SOLON TOWNSHIP, LEELANAU COUNTY, MICHIGAN







E. FOUCH ROAD

SHEET LIST

ENGINEER OF RECORD: BRIAN J. CENCI, P.E. #53847

SHEET NO.	REFERENCE NO.	DESCRIPTION
1	01-G-01	COVER SHEET
2	01-G-02	GENERAL NOTES AND LEGEND
3	01-G-03	SESC PLAN
4	02-C-01	P&P STA 0+00 TO STA 10+00
5	02-C-02	P&P STA. 10+00 TO STA. 18+00
6	02-C-03	P&P STA. 100+00 TO STA. 110+00
7	02-C-04	INFILTRATION BASIN DETAILS
8	02-C-05	PROPOSED ROAD FILL
9	99-D-01	TYPICAL CROSS SECTIONS
10	99-D-02	DETAILS 1
11	99-D-03	DETAILS 2
12	99-D-04	DETAILS 3

PROJECT & UTILITY CONTACTS

STEVEN CHRISTENSEN - LEELANAU COUNTY DRAIN COMMISSIONER SCHRISTENSEN@LEELANAU.GOV 8527 E. GOVERNMENT CENTER DR., SUITE #205 SUTTONS BAY, MI, 49682 O: (231) 256-8263

ENGINEER

BRIAN CENCI, P.E. - PROJECT MANAGER BCENCI@GEICONSULTANTS.COM C: (517) 449-3478

LEAH MARINO - PROJECT ENGINEER LMARINO@GEICONSULTANTS.COM C: (989) 550-4170

GEI CONSULTANTS OF MICHIGAN, P.C. 401 SOUTH WASHINGTON SQUARE, SUITE 103 LANSING, MI 48933

ROAD COMISSION (FOUCH RD. ONLY)

CRAIG BROWN, P.E.- ENGINEER LEELANAU COUNTY ROAD COMMISSION CBROWN@LEELANAUROADS.ORG 10550 E. ECKERLE RD. SUTTONS BAY, MI 48843 O: (231) 271-3993

UTILITY CONTACTS

JEFFREY SHUSTER - MANAGER OSP PLANNING & ENGINEERING DESIGN PHONE: (231) 510-1381 JS9865@ATT.COM

CHARTER COMMUNICATIONS

TWC_UTILITY_REQUESTS@CCISYSTEMS.COM

CHERRYLAND ELECTRIC COOPERATIVE JASON RICE - METERING SUPERVISOR PHONE: (231) 486-9200

JRICE@CHERRYLANDELECTRIC.COOP

DTE ENERGY - GAS

2230 US-10 LUDINGTON, MI 49431 PHONE: (231) 592-3244 LAWRENCE.BOURKE@DTEENERGY.COM

STEVEN CHRISTENSEN LEELANAU COUNTY DRAIN COMMISSIONER

LAKE BLUFFS DRAIN PART OF SECTION 14, SOLON TWP, R12W, LEELANAU COUNTY, MICHIGAN

COVER SHEET

Attention: If this scale bar does not measure 1" then drawing is

11/18/2022 MODIFIED FOR NOV. 2022 RE-BID

esigned By: LCM Checked By: MFS Drawn By: BSF

GEI PROJECT: 2003322 DWG. NO. 01-G-01

SHEET #1

CONTRACTOR SHALL MAINTAIN ACCESS FOR MAIL DELIVERY AND GARBAGE PICKLIP AT ALL PARCELS. IF THESE SERVICES CANNOT BE PERFORMED, THE CONTRACTOR IS RESPONSIBLE FOR TAKING THE NECESSARY MEASURES TO CARRY THEM OUT.

ALL SPRINKLER SYSTEMS DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR. COST IS TO BE INCLUDED IN OTHER WORK ITEMS OF THE PROJECT.

DRAINAGE SHALL BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION.

NO WORK SHALL BE PERFORMED BEFORE 7:00 AM OR AFTER 7:00 PM MONDAY THROUGH FRIDAY. NO WORK SHALL HAPPEN ON SATURDAYS, SUNDAYS, OR LEELANAU COUNTY HOLIDAYS UNLESS AUTHORIZED BY THE ENGINEER WITH AT LEAST 48 HOURS NOTICE PRIOR.

CONTRACTOR SHALL NOTIFY THE ENGINEER 48 HOURS PRIOR TO START OF CONSTRUCTION, CONSTRUCTION STAKING AND INSPECTION.

CONTRACTOR TO PROVIDE DUST CONTROL AND SWEEP ADJACENT ROADS DAILY, OR SEVERAL TIMES A DAY, SHOULD CONDITIONS REQUIRE.

ALL EXCAVATED MATERIAL NOT DESIGNATED FOR RELISE SHALL BE REMOVED FROM SITE ALTIME OF DISTURBANCE OR AS APPLICABLE. IF MATERIAL IS UNABLE TO BE REMOVED AT TIME OF DISTURBANCE, THE MATERIAL SHALL BE STOCKPILED ACCORDING TO THE SESC PLAN AND REMOVED PRIOR TO STORM EVENTS. THE CONTRACTOR IS RESPONSIBLE FOR POSING MATERIALS ACCORDING TO LOCAL AND STATE REQUIREMENTS.

ALL WORK SHALL BE WITHIN DRAIN RIGHT-OF-WAY OR PRIVATE ROAD RIGHT-OF-WAY. WORK OUTSIDE RIGHT-OF-WAY MIUST BE AGREED UPON BY LANDOWNER AND ENCINEER WITH A SIGNED LANDOWNER AGREEMENT PRIOR TO WORK ON THAT PROPERTY.

THE CONTRACTOR IS TO RESTORE INCIDENTAL DAMAGES ON THE PROJECT AS DIRECTED BY THE ENGINEER.

ALL DRAIN SIDE SLOPES SHALL BE 2H:1V OR FLATTER, UNLESS SPECIFIED OTHERWISE.

THE WORDS "RIGHT SIDE" OR "LEFT SIDE" IMPLY A REFERENCE TO THE DRAIN FACING

CLEAR AND GRUB TREES AS INDICATED FOR CONSTRUCTION WITHIN DRAIN RIGHT-OF-WAY REMOVE ALL TREES, STUMPS AND DEBRIS FROM SITE.

REMOVE EXISTING FENCES, LANDSCAPING, AND OTHER STRUCTURES IN DRAIN RIGHT-OF-WAY AS INDICATED ON THE PLANS. REMOVAL AND REINSTALLATION COST TO BE INCLUDED IN SITE CLEARING OR OTHER PAY ITEMS, PER CONTRACT DOCUMENTS.

CONTRACTOR SHALL COORDINATE REMOVAL OF ALL TREES WITHIN THE LIMITS OF CONSTRUCTION WITH THE ENGINEER.

DRAINAGE SHALL BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION.

PERMANENT SIGNS
ANY PERMANENT SIGNS OR STREET SIGNS REQUIRING RELOCATION DUE TO CONTRACTOR OPERATIONS SHALL BE SALVAGED AND RESET BY THE CONTRACTOR AT LOCATIONS DESIGNATED BY THE ENGINEER. SIGNS AND POSTS DAMAGED DURING THE REMOVAL AND STAGE OPERATIONS SHALL BE REPLACED WITH NEW SIGNS AND POSTS.

PAVEMENT REMOVAL
PAVEMENT REMOVAL AS SHOWN ON THE PLANS SHALL BE AT THE DISCRETION OF THE
ENGINEER. IF IN HIS/HER JUDGEMENT, AREAS OF PAVEMENT MAY BE LEFT IN PLACE, OR
ADDITIONAL AREAS ADDED, TO PROVIDE THE PROPER CROSS-SECTION AND BASE
ADJUSTMENTS CAN BE MADE IN THE QUANTITIES.

UTILITIES
FOR THE PROTECTION OF UNDERGROUND UTILITIES AND IN CONFORMANCE WITH PUBLIC ACT 53, 1974, THE CONTRACTOR SHALL DIAL 1-800-482-7171 A MINIMUM OF THREE FULL WORKING DAYS, EXCLUDING SATURDAYS, SUNDAYS, MINIMUM OF I HEEF DELE WORKING DATS, EXCLUSIVES SATURDATS, SUNDATS, AND HOLIDAYS PRIOR TO BEGINNING EACH EXCAVATION IN AREAS WHERE PUBLIC UTILITIES HAVE NOT BEEN PREVIOUSLY LOCATED. MEMBERS WILL THUS BE ROUTINELY NOTIFIED. THIS DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY OF NOTIFIEN UTILITY OWNERS WHO MAY NOT BE A PART OF THE WARD ON THE HEAD TO STATE THE CONTRACTOR.

THE EXISTING UTILITIES ON THESE DRAWINGS HAVE BEEN SHOWN ACCORDING TO THE BEST AVAILABLE INFORMATION. THE CONTRACTOR SHALL FIELD LOCATE ALL UTILITIES PRIOR TO BEGINNING CONSTRUCTION AND SHALL NOTIFY THE ENGINEER AS TO WHERE POSSIBLE CONFLICT EXISTS

ELECTRIC, GAS, AND COMMUNICATION UTILITIES LOCATED IN THE ROAD AND DRAIN RIGHT-OF-WAYS MUST BE LOCATED PRIOR TO EXCAVATION WORK AND ELEVATIONS MUST BE PROVIDED TO ENGINEER TO CONFIRM NO CONFLICTS EXIST. CONTRACTOR SHALL NOTIFY THE ENGINEER AS TO WHERE POSSIBLE CONFLICTS EXIST.

ANY UTILITIES DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

ALL MANHOLE RIMS IN ROADWAYS AND DRIVES SHALL BE ADJUSTED PRIOR TO FINAL PAVING TO BE FLUSH WITH FINISHED GRADE.

GRADING AROUND MANHOLES/CATCHBASINS, FLARED END SECTIONS, AND OTHER INLETS DETERMINED BY THE ENGINEER SHALL BE SMOOTH AND SHAPED TO PROVIDE POSITIVE DRAINAGE INTO THE INLETS.

ALL MANHOLE TO PLASTIC PIPE CONNECTIONS SHALL BE MADE WITH KOR-N-SEAL BOOT OR ENGINEER APPROVED EQUAL.

ALL CORRUGATED METAL PIPE SHALL BE TYPE II ALUMINIZED UNLESS OTHERWISE NOTED

ALL STORM SEWER ARE TO BE PREMIUM JOINT UNLESS OTHERWISE SPECIFIED.

ALL FLARED END SECTIONS ARE TO HAVE FACTORY SUPPLIED ANIMAL GUARD.

DEMOLISH EXISTING STRUCTURE(S) AND DISPOSE OF IN ACCORDANCE WITH LOCAL, STATE, AND FEDERAL REQUIREMENTS. COST TO BE INCLUDED WITH THE ITEM BEING INSTALLED AS DIRECTED BY ENGINEER.

CONTRACTOR SHALL CONNECT ANY AND ALL FIELD TILE OUTLETS AND OTHER STORM LEADS TO PROPOSED STORM SEWER WITH PREMANUFACTURED TEES, WYES, GASKETS, SEALS, COUPLERS, BOOTS, ETC. COST IS TO BE INCLUDED IN UNIT BID PRICE FOR STORM

ALL LITH ITY POLES IMPACTED DURING CONSTRUCTION SHALL BE SUPPORTED IF NECESSARY, PER THE SPECIFICATIONS OF THE INDIVIDUAL UTILITY COMPANY

ALL UTILITIES ENCOUNTERED DURING CONSTRUCTION SHALL BE PROTECTED, PER REQUIREMENTS OF THE INDIVIDUAL UTILITY COMPANY.

PROPERTY OWNERS PROPERTY OWNERS NAMES, WHERE SHOWN, ARE FOR INFORMATION ONLY AND THEIR ACCURACY IS NOT GUARANTEED.

PROPERTY CORNER MONUMENT VISIBILY OBSERVED ON SITE, WHETHER SHOWN OR NOT, SHALL BE PROTECTED. DAMAGED PROPERTY CORNERS WILL BE RESET AT CONTRACTOR'S EXPENSE.

ADJUSTING MONUMENT BOXES
ALL GOVERNMENT CORNERS ON THIS PROJECT SHALL BE PRESERVED IF ENCOUNTERED,
WHETHER SHOWN OR NOT. IT MAY BE NECESSARY TO PLACE OR ADJUST MONUMENT

TRAFFIC CONTROL
THE CONTRACTOR SHALL MAINTAIN LOCAL TRAFFIC AT ALL TIMES.

PERMITS
PRIOR TO COMMENCING CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR ORTAINING ALL PERMITS REQUIRED BY THE APPROPRIATE AGENCIES ANY REQUIRED PERMITS ARE LISTED IN THE CONTRACT DOCUMENTS, SECTION 01010 - SUMMARY OF WORK.

CONSTRUCTION PROCEDURES SHALL CONFORM TO THE REQUIREMENTS OF THE

MAILBOXES & TRASH PICKUP
THE CONTRACTOR SHALL REMOVE AND TEMPORARILY RELOCATE ALL EXISTING MAIL
BOXES AS NEEDED FOR CONSTRUCTION.

THE CONTRACTOR SHALL COORDINATE MAIL BOX RELOCATION WITH LANDOWNERS A MINIMUM OF ONE DAY IN ADVANCE.

ALL TEMPORARILY RELOCATED MAIL BOXES, STREET AND TRAFFIC SIGNS ARE TO BE REINSTALLED TO ORIGINAL LOCATIONS AS CONSTRUCTION ALLOWS.

CONTRACTOR WILL COORDINATE, MOVE TRASH BINS FROM END OF DRIVEWAYS TO NEAR FOUCH RD. ON DAY OF PICKUP TO CONTINUE TO ALLOW FOR TRASH PICKUP SERVICES.

PAVED SURFACES - ROADS, DRIVEWAYS, PATHS, AND SIDEWALKS COORDINATE DRIVEWAY CLOSURES WITH LANDOWNERS A MINIMUM OF 48 HOURS IN ADVANCE.

ALL JOINTS AT INTERSECTION APPROACHES AND DRIVEWAYS SHALL BE SAW-CUT WITH BUTT-JOINTS UNLESS OTHERWISE NOTED. THE COST IS TO BE INCLUDED IN UNIT PRICE FOR ROAD AND DRIVEWAY REPAIR.

ALL DRIVING SURFACES ARE TO BE RESTORED TO IN-KIND DEPTH AND MATERIAL UNLESS OTHERWISE SPECIFIED ON THE PLANS.

PROTECT ALL BITUMINOUS ROADS NOT SPECIFIED TO BE REMOVED DURING CONSTRUCTION. REPAIR ANY UNAUTHORIZED DAMAGE AT CONTRACTORS EXPENSE.

BROKEN CONCRETE AND DEBRIS SHALL BE CONSIDERED WASTE AND SHALL BE DISPOSED OF BY THE CONTRACTOR OFF SITE. COST OF WORK CONSIDERED INCIDENTAL TO CONSTRUCTION.

CONTRACTOR SHALL REMOVE ALL STREET AND/OR PRIVATE TRAFFIC SIGNAGE AS IS NEEDED FOR CONSTRUCTION AND SHALL RESTORE AFTER CONSTRUCTION WORK IS COMPLETED. ALL ASSOCIATED COSTS FOR THIS WORK TO BE CONSIDERED INCIDENTAL TO

ALL WORK WITHIN THE ROAD RIGHT-OF-WAY SHALL BE IN ACCORDANCE WITH THE CURRENT STANDARDS AND GENERAL SPECIFICATIONS OF SOLON TOWNSHIP, LEELANAU COUNTY ROAD DEPARTMENT, WHERE APPLICABLE.

AGGREGATE BASE

AGGREGATE BASES SHALL USE MDOT AGGREGATE 22A, UNLESS OTHERWISE SPECIFIED.

THE WORK REPRESENTED BY THIS DRAWING WAS DESIGNED BY THE ENGINEER FOR THIS SPECIFIC APPLICATION AND SPECIFIC LOCATION DESCRIBED HEREON IN ACCORDANCE WITH THE CONDITIONS PREVALENT AT THE TIME THE DESIGN WAS DONE. THE ENGINEER DOES NOT GUARANTEE AND WILL NOT BE LIABLE FOR ANY OTHER LOCATION, CONDITION, DESIGN OR PURPOSE.

LINETYPES

DRAINAGE UTILITIES EXISTING PROPOSED DESCRIPTION — — UNDER DRAIN (DRAIN TILE) — CULVERT LINE CULVERT HEAD OR WING WALL — — — DRAINAGE BASIN OUTLINE (FDGE OF WATER) ROADWAY EXISTING - GRAVEL PROPOSED - ASPHALT DESCRIPTION EDGE OF ROADWAY ELECTRICAL POWER EXISTING PROPOSED DESCRIPTION NATURAL GAS FXISTING PROPOSED DESCRIPTION — GAS — GAS UG NATURAL GAS GENERAL/COMMUNICATION EXISTING PROPOSED DESCRIPTION — сомм — — COMM— UG COMCAST MISCELLANEOUS EXISTING PROPOSED DESCRIPTION _____ x ____ x ____ FENCE LINE TREE LINE

SYMBOLS

DRAINAGE UTILITIES				MISCELLANEOUS		
EXISTING	PROPOSED	DESCRIPTION	EXISTING	PROPOSED	DESCRIPTION	
# D O	⊕ 🖸 🗸 🖶	CATCH BASIN (ROUND) CATCH BASIN (SQUARE) END SECTION INVERT ELEVATION	EXISTING	COMMUNICA PROPOSED	MAIL BOX SIGN POST ATION DESCRIPTION	
	VEGETATION			C F	CABLE PEDESTAL FIBER PEDESTAL	
EXISTING	PROPOSED	DESCRIPTION	E		TELEPHONE PEDESTAL	
0	⊖	BUSH OR SHRUB	F	(F)	MANHOLE FIBER	
	A A	STUMP DECIDUOUS TREES	① Ø	① Ø NATURAL (MANHOLE TELEPHONE TELEPHONE POLE	
	ELECTRICAL PO	OWER	EXISTING	PROPOSED	DESCRIPTION	
EXISTING	PROPOSED	DESCRIPTION	©	©	NATURAL GAS METER	
E	E	ELECTICAL PEDESTAL	© ©	● ©	UG NATURAL GAS VALVI NATURAL GAS MANHOLI	

DRAWING NUMBER DESIGNATION



DISCIPLINE IDENTIFER

DISCIPLINE	DISCIPLINE IDENT
GENERAL	G
REMOVAL	R
CIVIL - PLAN PROFILE	С
DETAILS	D

1. STRUCTURE IDENTIFIER SHALL BE 01 FOR

2. STRUCTURE IDENTIFIER SHALL BE 02 FOR

3. STRUCTURE IDENTIFIER SHALL BE 99 FOR STANDARD DETAILS.

ABBREVIATIONS

ASPH	ASPHALT	IE	INVERT ELEVATION	
в то в	BACK TO BACK	IGLD	INTERNATIONAL GREAT LAKES DATUM	
BM	BENCH MARK	IL	INLET	
BS	BACKSLOPE	IN	INCH	
B/C	BACK OF CURB	INSP	INSPECTION	
BIT	BITUMINOUS	INTER	INTERSECTION	
BR	BRIDGE	LB	POUND	
CL	CENTERLINE	LEVCSE	LEVEL COURSE	
C&G	CURB & GUTTER	LFT	LINEAL FEET	
СВ	CATCH BASIN	LLV	LONG LEGNTH VERTICAL	
CI	CAST IRON PIPE	LSUM	LUMP SUM	
co	SANITARY SEWER CLEANOUT	LWL	LOW WATER LEVEL	
CSP	CORRUGATED STEEL PIPE	MH	MANHOLE	
C-C	CENTER TO CENTER	MAINT	MAINTENANCE	
CEN CEN	CENTER TO CENTER	MGD	MILLION GALLONS PER DAY	
CIP	COMPACTED IN PLACE	MGD	MONUMENT	
CMP	COMPACTED IN PLACE CORRUGATED METAL PIPE	MON	NATIONAL GEODETIC VERTICAL DATUM	
CMP			ON CENTER	
	COMPINED	oc		
COMB	COMBINED	OF	OVERFLOW	
COMP	COMPACTED	ОН	OVERHEAD	
CONC	CONCRETE	PL	PROPERTY LINE	
CONST	CONSTRUCT	PP	POWER POLE	
COR	CORNER	PAVT	PAVEMENT	
CORR	CORRUGATED	PROJ	PROJECT	
CR	CREEK	PPTY	PROPERTY	
CTE	CONNECT TO EXISTING	PROP	PROPOSED	
CULV	CULVERT	RB	ROUND BOTTOM	
CYD	CUBIC YARDS	RR	RAILROAD	
CS&B	CURB STOP AND BOX	RCP	REINFORCED CONCRETE PIPE	
DIP	DUCTILE IRON PIPE	RDY	ROADWAY	
DEFL	DEFLECTION	REINF	REINFORCING OR REINFORCEMENT	
DET	DETAIL	ROW	RIGHT OF WAY	
DR	DRIVE	SG	SUBGRADE	
DWY	DRIVEWAY	SW	SIDEWALK	
EG	EARTHGRADE	SALV	SALVAGED	
EGL	ENERGY GRADE LINE	SAN	SANITARY SEWER	
EL	ELEVATION	SXN	SECTION	
ELEC	ELECTRIC	SEC	SECTION (LAND SURVEY)	
ELEV	ELEVATION	SEW	SEWER	
EMB	EMBANKMENT	SFT	SQUARE FEET	
ENC	ENCASED	SHLD	SHOULDER	
ENG	ENGINEER	SIG	SIGNAL	
EX	EXISTING	SPC	SPECIAL	
EXC	EXCAVATION	SPEC	SPECIFICATIONS	
EXIST	EXISTING	SPECPROV	SPECIAL PROVISIONS	
EXP	EXPANSION	STDSPEC	STANDARD SPECIFICATIONS	
FI	FLOW LINE	STM	STANDARD SPECIFICATIONS STORM SEWER	
FM	FORCE MAIN	SUB	SUBBASE	
	FORCE MAIN FACE CURB	SURF	SUBBASE	
F/C F-F			SURFACE SQUARE YARDS	
	FACE TO FACE OF CURB	TCSE	SQUARE YARDS TOP COURSE	
FL				
	FOOT/FEET	TDH	TOTAL DYNAMIC HEAD	
FTG	FOOTING	TRANS	TRANSMISSION	
GDE	GRADE	TWP	TOWNSHIP	
GR	GUARD RAIL	TYP	TYPICAL	
GAL	GALLONS	UG	UNDERGROUND	
GPD	GALLONS PER DAY	UNIF	UNIFORM	
GPM	GALLONS PER MINUTE	VFT	VERTICAL FEET	
HDW	HEADWALL	VCP	VITRIFIED CLAY PIPE	
HGL	HYDRAULIC GRADE LINE	WM	WATER MAIN	
HWI	HIGH WATER LEVEL	ws	WATER SERVICE	
· · · · · · ·	i .			

CROSS SECTIONS HATCH LEGEND

MATERIAL DESCRIPTION	PROPOSED WORK PATTERN
RIPRAP, PLAN	
CHECK DAMS, SESC PLAN (SHEET 3)	
RIPRAP DIVERSIONS, PLAN	
TOPSOIL SURFACE, FURN, 3 INCH; SEEDING, MIXTURE THM, FERTILIZER, AND MULCH	
HMA, PLAN	
BERM, PLAN	

Attention:

SMART DITCH, PLAN

401 S. WASHINGTON SQUARE

STEVEN CHRISTENSEN COUNTY DRAIN COMMISSIONE LAKE BLUFFS DRAIN PART OF SECTION 14, SOLON TWP, R12W, LEELANAU COUNTY, MICHIGAN LANAU A I T28N,

> AND NOTES

Щ

If this scale bar does not measure 1" then drawing is not original scale.

RELEASE # DATE DESCRIPTION 6/9/2022 11/18/2022 MODIFIED FOR NOV. 2022 RE-BID

Designed By: LCM Checked By: MFS

Drawn By: BSF GELPROJECT: 2003322

> DWG. NO. 01-G-02

> > SHFFT #2

	KEY	LOCATION	DESCRIPTION	
£	1 P	ALL DISTURBED AREAS	SEEDING	
100	2 P	ALL DISTURBED AREAS	MULCH/MULCH BLANKET	
43	7	*CATCH BASINS	STORM DRAIN INLET PROTECTION	
1	(10 P	ALL DISTURBED AREAS	SOIL BINDING POLYMERS	
0.00	(15) P	AT INLETS/OUTLETS	RIPRAP	
	23 P	ALL OUTLETS	OUTFALL STABILIZATION	9
-	26 T	ENTIRE SITE	DUST CONTROL	
	29 P	DITCHES	PERMANENT CHECK DAM	
	36 P	INFILTRATION BASINS	SEDIMENT BASIN	
	TOTAL LIMITS OF DISTURBANCE = 1.65 AC		LOD LOD	

AT TIME OF CATCH BASIN COVER INSTALLATION. COORDINATE WITH ENGINEER.

SOIL EROSION AND SEDIMENTATION CONTROL NOTES

- TEMPORARY MEASURES SHALL BE INSTALLED PRIOR TO OR UPON COMMENCEMENT OF EARTH CHANGE ACTIVITY AT EACH SITE
- THE CONTRACTOR SHALL CONFORM TO SOIL EROSION AND SEDIMENTATION CONTROL ACT, PART 91 OF ACT 451 OF 1994 AND MUST PROVIDE NOTICE TO THE CEA PRIOR TO THE START OF CONSTRUCTION
- THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT MEASURES ARE INSTALLED IN COMPLIANCE WITH THE MANUFACTURERS RECOMMENDATIONS, AND THE PLANS. THE CONTRACTOR IS RESPONSIBLE TO ENSURE THAT THE SESC MEASURES ARE MONITORED AND MAINTAINED UNTIL ALL DISTURBED AREAS ARE STABILIZED AND TEMPORARY MEASURES ARE REMOVED. THE CONTRACTOR ACKNOWLEDGES THAT SESC MEASURES MAY NEED TO BE ADAPTED, ADJUSTED, OR ADDED BASED ON SITE CONDITIONS IN ORDER TO REMAIN IN COMPLIANCE WITH PART 91 REQUIREMENTS
- ALL SOIL EROSION CONTROL MEASURES SHALL BE INSPECTED AND MAINTAINED DAILY BY THE CONTRACTOR. THE CONTRACTOR SHALL INSPECT AFTER EACH RAIN EVENT TO ENSURE PROPER MAINTENANCE OF THE SOIL EROSION CONTROL MEASURES. ANY DEFICIENCIES OR REPAIRS TO SOIL EROSION CONTROL MEASURES ARE TO BE
- THE CONTRACTOR SHALL INSTALL FINAL SOIL EROSION CONTROL MEASURES WITHIN 72 HOURS OF FINAL GRADE IN ANY AREA (GRADE LISTED ON PLANS) UNLESS SPECIFIED OTHERWISE BY ENGINEER. WEEKLY INSPECTIONS OF SEEDED AREAS SHALL BE COMPLETED TO VERIFY GRASS GROWTH. ANY AREAS NOT ESTABLISHED SHALL BE FERTILIZED, SOILS AMENDED AND RE-SEEDED AS NECESSARY, ALL COST FOR ESTABLISHMENT OF SEEDED AREAS SHALL BE INCLUDED IN THE UNIT BID PRICE FOR THE SPECIFIC SEEDING BEING INSTALLED.
- THE CONTRACTOR SHALL REMOVE TEMPORARY SOIL EROSION AND SEDIMENTATION CONTROL MEASURES WITHIN 45 DAYS AFTER PERMANENT SOIL EROSION MEASURES ARE IN PLACE AND THE AREA IS STABILIZED ("STABILIZED" MEANS THE ESTABLISHMENT OF VEGETATION OR THE PROPER PLACEMENT, GRADING, OR COVERING OF SOIL TO ENSURE ITS RESISTANCE TO SOIL EROSION, SLIDING, OR OTHER EARTH MOVEMENT)
- REMOVAL OF TEMPORARY MEASURES IS THE RESPONSIBILITY OF THE CONTRACTOR.
- THE CONTRACTOR IS RESPONSIBLE FOR CLEANUP & RESTORATION INCLUDING PROGRESS CLEANING, PROGRESS CLEANING INCLUDES BUT IS NOT LIMITED TO REMOVAL OF WASTE MATERIALS, DEBRIS, RUBBISH, AND EXCESS SPOILS, COMPLETE LEVELING AND DAMAGE RESTORATION AT REGULAR INTERVALS DURING CONSTRUCTION.
- SEDIMENTS CAUSED BY ACCELERATED SOIL EROSION SHALL BE REMOVED FROM RUNOFF WATER BEFORE IT
- 10. PLACE TURE ESTABLISHMENT ITEMS AS SOON AS POSSIBLE ON POTENTIAL ERODABLE SLOPES AS DIRECTED BY THE ENGINEER. CRITICAL DITCH GRADES SHALL BE PROTECTED WITH SOD OR SEED/MULCH OR MULCH BLANKET AS DIRECTED BY THE ENGINEER.
- 11. IE NECESSARY A TEMPORARY CONTROL MEASURE SHALL BE DESIGNED AND CONSTRUCTED FOR THE CONVEYANCE OF WATER AROUND, THROUGH OR FROM THE EARTH CHANGE AREA TO LIMIT WATER FLOW TO A NON-EROSIVE VELOCITY.
- 12. MAINTAIN ON SITE OR HAVE READILY AVAILABLE SUFFICIENT OIL AND GREASE ABSORBING MATERIALS AND FLOTATION BOOMS TO CONTAIN AND CLEAN UP FUEL OR CHEMICAL SPILLS AND LEAKS. NO SPILLED CHEMICALS OR PETROLEUM OR VEHICULAR ELUIDS ARE TO COME INTO CONTACT WITH DRAINAGE DITCHES. WETLAND OR WATERS OF THE STATE
- 13. ALL SLOPES AND AREAS DISTURBED BY CONSTRUCTION SHALL BE GRADED AND THREE INCHES OF TOPSOIL APPLIED, EXISTING TOPSOIL MAY BE USED FOR RESTORATION OF THIS ACTIVITY WHERE INDICATED. IF ADEQUATE TOPSOIL IS NOT AVAILABLE ON SITE THE CONTRACTOR SHALL PROVIDE THE TOPSOIL, APPROVED BY THE OWNER AND ENGINEER, AS NEEDED. THE AREA SHALL BE SEEDED, FERTILIZED, WATERED AND MAINTAINED UNTIL VEGETATION IS WELL ESTABLISHED. NOTE: FERTILIZER SHALL NOT BE USED WITHIN 50 FEET OF THE RIVER. LAKE OR STREAM AT THIS SITE. ANY AREAS DISTURBED FOR ANY REASON PRIOR TO FINAL ACCEPTANCE OF THE PROJECT WILL BE CORRECTED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- 14. THE CONTRACTOR WILL WATCH FOR WEATHER CHANGES THAT WILL CREATE EROSION CONDITIONS AND WILL APPLY EROSION CONTROL MEASURES BEFORE A STORM HITS THE SITE.
- 15. STOCKPILES OF MATERIALS SHALL BE COVERED AND PROTECTED IN A MANNER TO PREVENT SILTATION OF SURROUNDING SITE OR EROSION FROM OCCURRING ON THE STOCKPILE.
- 16. NO WORK THAT REQUIRES DEWATERING SHALL COMMENCE WITHOUT APPROVAL FROM THE ENGINEER. WATER DISCHARGED FROM DEWATERING SHALL NOT EXCEED 200 NTU
- 17. THE CONTRACTOR IS RESPONSIBLE FOR THE SESC PERMIT, IF APPLICABLE, AT ANY SPOIL DEPOSIT LOCATIONS. LOCATIONS MUST BE APPROVED BEFORE DEPOSITION.
- 18. THE DRAIN COMMISSIONER MAY ASSESS COST FOR SITE RESTORATION, SITE STABILIZATION, AND/OR RESTORE OR REPAIR OFF-SITE DAMAGES IF THE CONTRACTOR DOES NOT COMPLY WITH THEIR CONTRACT OR PART 91.
- 19. DETAILED DRAWINGS AND SPECIFICATIONS ARE LOCATED IN THE MICHIGAN ASSOCIATION OF COUNTY DRAIN COMMISSIONERS SOILS EROSION AND SEDIMENTATION CONTROL AUTHORIZED PUBLIC AGENCY PROCEDURES
- 20. MEASURES SHALL ONLY BE PAID FOR ONCE

ALL AREAS DISTURBED DURING CONSTRUCTION TO BE RESTORED PER SPECIFICATIONS.

SLOPE AND DITCH RESTORATION SHALL BE PER MDOT'S SPECIAL PROVISION FOR SLOPE

RUNNING SLOPES GREATER THAN 3% AND ON ALL SLOPES GREATER THAN 1 ON 3 MULCH BLANKET SHALL BE USED ON ALL AREA WITH 1 ON 3 SLOPES.

ALL GRADES, DITCHES, SLOPES, ETC. SHALL BE RESTORED TO PRE-EXISTING OR BETTER CONDITIONS. THIS INCLUDES THE INSTALLATION OF RIP-RAP, DITCHES, CHECK DAMS,

PAYMENT FOR RESTORATION SHALL BE AS SHOWN ON THE PLANS AND PER THE PAY

HIGH VELOCITY MULCH BLANKET SHALL BE USED IN ALL DITCH BOTTOMS WIT

MULCH SHALL BE USED ON ALL AREAS WITH SLOPES LESS THAN 1 ON 3

AND OTHER EROSION CONTROL ITEMS. PAYMENT FOR THIS WORK IS INCIDENTAL

ITEMS IN THE BID SCHEDULE.

RESTORATION, NON-FREEWAY,

UNLESS OTHERWISE CALLED OUT.

SOIL EROSION & SEDIMENTATION CONTROL TABLE

1 P	ALL DISTURBED AREAS	SEEDING		
(2) P	ALL DISTURBED AREAS	MULCH/MULCH BLANKET		
7	*CATCH BASINS	STORM DRAIN INLET PROTECTION		
(10) P	ALL DISTURBED AREAS	SOIL BINDING POLYMERS		
(15) P	AT INLETS/OUTLETS	RIPRAP		
23 P	ALL OUTLETS	OUTFALL STABILIZATION		
(26) T	ENTIRE SITE	DUST CONTROL		
(29) P	DITCHES	PERMANENT CHECK DAM		
36 P	INFILTRATION BASINS	SEDIMENT BASIN		
TOTAL LIMITS OF DISTURBANCE = 1.65 AC		LOD		
ONCE CATCH BASIN COVERS AND CASTINGS ARE INSTALLED CATCH BASINS INLET				

ONCE CATCH BASIN COVERS AND CASTINGS ARE INSTALLED, CATCH BASINS INLE PROTECTION SHALL BE FURNISHED IF ALL DISTURBED AREAS ARE NOT STABILIZED

MAINTENANCE PROGRAM FOR SESC MEASURES

GENERAL MAINTENANCE

- TEMPORARY SESC MEASURES SHALL BE INSTALLED, MAINTAINED, AND REMOVED BY THE CONTRACTOR
- TEMPORARY SESC MEASURES SHALL BE INSTALLED PRIOR TO OR UPON COMMENCEMENT OF ANY EARTH
- TEMPORARY MEASURES MUST BE MAINTAINED AND IN PLACE UNTIL AREAS ARE PERMANENTLY
- TEMPORARY SESC MEASURES SHALL BE REMOVED AT THE END OF THE PROJECT ONCE PERMANENT MEASURES ARE IN PLACE AND DISTURBED AREAS ARE STABILIZED
- PERMANENT MEASURES SHALL BE INSTALLED AND MAINTAINED BY THE CONTRACTOR UNTIL FINAL
- DAILY MAINTENANCE IS THE CONTRACTORS RESPONSIBILITY

- INSPECT NEWLY SEEDED AND MULCHED AREAS SUBSEQUENT TO ANTICIPATED GERMINATION DATE AND AFTER EACH SIGNIFICANT RAINFALL EVENT THAT PRODUCES RUNOFF UNTIL AREAS ARE STABILIZED AND TO CHECK FOR MOVEMENT OR EROSION.
- INSPECT MULCHED AREAS ROUTINELY AND AFTER EACH SIGNIFICANT RAINFALL EVENT TO CHECK FOR MOVEMENT OR EROSION UNTIL AREAS ARE STABILIZED. IF WASHOUTS OR EROSION OCCUR, REPAIR THE SURRACE, RE-SEED AND RE-MULCH. CONTINUE INSPECTIONS AS NECESSARY UNTIL VEGETATION IS FIRMLY ESTABLISHED
- REPAIR ERODED AREAS, APPLYING SUPPLEMENTAL SEED, MULCH, AND WATER AS NEEDED
- IF SEED DOES NOT ESTABLISH, CONDUCT SOIL TESTS, AMEND SOILS AS NEEDED, AND REAPPLY SEED AND/OR MULCH DURING THE RECOMMENDED GROWING SEASON
- TO ASSIST IN THE ESTABLISHMENT OF NATIVE SPECIES, REMOVE UNWANTED COMPETING VEGETATION IN
- MOWING DURING ESTABLISHMENT CAN BE USED PERIODICALLY TO DISCOURAGE WEEDS

SOIL BINDING POLYMERS

- APPLY EVERY TIME SEED IS PLACED
- VISUALLY INSPECT ALL AREAS WHERE THE POLYMER HAS BEEN APPLIED WITHOUT WALKING OR TRAVELING OVER THE AREA FOLLOWING EACH SIGNIFICANT PRECIPITATION OR WIND EVENT AND PRIOR TO EXPECTED EVENTS. REAPPLY IF SOIL AREAS INDICATED DISTURBANCE BY EROSIVE FORCES, OR IF DEEMED NECESSARY, REAPPLY IN CONJUNCTION WITH ADDITIONAL MANAGEMENT PRACTICES.
- REAPPLY IF TREATED AREA IS DISRUPTED OR SHOWS SIGNS OF DISTURBANCE FROM EROSION FORCES

- IF RIPRAP HAS BEEN DISPLACED AND THE GEOTEXTILE FABRIC IS DAMAGED DURING HIGH FLOW IF RIPARP FIAS BEEN DISPLACED AND THE GEOTEXTILE FABRIC IS DAVIAGED DURING HIGH FLOW CONDITIONS OR FROM VANDALISM, REMOVE RIPRAP AND REPAIR GEOTEXTILE FABRIC BY ADDING ANOTHER LAYER OVERLAPPING THE DAMAGED AREA BY 2 FEET AND ANCHORING WITH PINS SPACED 3 FEET APART. REPLACE RIPRAP OVER GEOTEXTILE FABRIC.
- INSPECT FOLLOWING EACH PRECIPITATION THAT RESULTS IN RUNOFF AND CONFIRM EFFECTIVENESS, MAKE NECESSARY ADJUSTMENTS. EXPAND RIPRAP AREAS AS NEEDED.

OUTFALL STABILIZATION

INSPECT FOLLOWING SUBSEQUENT OUTFALL DISCHARGE EVENT FOR ANY SCOUR/EROSION AT THE OUTFALL POINT AND ON OPPOSITE BANK, REPAIR/MODIFY AND MONITOR UNTIL AREA IS STABILIZED.

DUST CONTROL

SWEEP FOLICH ROAD DAILY OR SEVERAL TIMES A DAY SHOULD CONDITIONS PROVIDE.

- INSPECT CHECK DAMS FOLLOWING EACH RUNOFF EVENT TO ENSURE THERE IS NO PIPING UNDER THE STRUCTURE OR AROUND THE BANKS UNTIL THE FLOW CORRIDOR HAS BEEN STABILIZED.
- REMOVE AND PROPERLY DISPOSE OF SEDIMENT WHEN IT ACCUMULATES TO 1/2 THE CHECK DAM HEIGHT
- INSPECT DOWNSTREAM STRUCTURES TO ENSURE THEY HAVE NOT BEEN DAMAGED OR CLOGGED WITH DISPLACED ROCK OR STONE.
- CHECK DAMS SHOULD BE CONSTRUCTED OF CLEAN ROCK PLACED ON GEOTEXTILE FABRIC WHICH HAS BEEN TOED IN A MINIMUM OF 3 INCHES.

SEDIMENT BASIN

- INSPECT ROUTINELY, PARTICULARLY FOLLOWING RUNOFF EVENTS, TO ASSESS EFFECTIVENESS AND MONITOR DEBRIS AND SEDIMENT ACCUMULATION.
- KEEP INLET AND OUTLET FREE OF DEBRIS ACCUMULATION TO MAINTAIN PROPER FLOW
- SEDIMENT SHALL BE REMOVED AND THE BASIN RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE BASIN.

CONTINUED MAINTENANCE PLAN

THE CONTRACTOR SHALL MAINTAIN ALL PERMANENT SESC MEASURES FOR A PERIOD OF 1 YEAR FOLLOWING PROJECT COMPLETION, THIS INCLUDES VEGETATION ESTABLISHMENT.

PROPOSED EARTH CHANGE

• EARTH CHANGE INCLUDES DITCH INSTALLATION, GRADING AND STORM SEWER INSTALLATION.

PROXIMITY TO LAKES AND STREAMS

EARTH CHANGE IS 800 FEET FROM LAKE LEELANAU

COMPLIANCE WITH PART 91 OF PA 451

- ALL CONTRACTORS AND SUBCONTRACTORS INVOLVED WITH AN EARTH DISTURBANCE ACTIVITY SHALL BE PROVIDED A COPY OF THIS SOIL EROSION CONTROL PLAN AND STRICTLY ADHERE TO ITS REQUIREMENTS
- 2. THE CONTRACTOR IS RESPONSIBLE TO INSTALL AND MAINTAIN APPLICABLE SOIL EROSION AND SEDIMENTATION CONTROL MEASURES IN ACCORDANCE WITH THE APPROVED PLANS PRIOR TO COMMENCEMENT OF CONSTRUCTION, MASS GRADING, OR STAGING WORK, THE CONTRACTOR SHALL CONFORM TO SOIL EROSION AND SEDIMENTATION CONTROL ACT, PART 91 OF ACT 451 OF 1994
- 3. INSPECTION BY A CERTIFIED STORM WATER OPERATOR FOR CONSTRUCTION SITES WILL TAKE PLACE WEEKLY AND AFTER EACH RAINEALL EVENT THAT PRODUCES RUNGE FROM THE SITE PROPE DOCUMENTATION OF THE INSPECTIONS WILL BE MAINTAINED AS PER PART 91 OF PA 451 OF 1994.
- RESPOND IMMEDIATELY TO STORMWATER OPERATOR AND/OR SOIL FROSION AND SEDIMENTATION CONTROL INSPECTOR CONCERNS. MAKE CORRECTIVE MEASURES AS REQUIRED IMMEDIATELY
- 5. IF FOR ANY REASON THE OWNER IS FOUND TO BE IN VIOLATION OF PART 91 DUE TO CONTRACTOR'S NONCOMPLIANCE, THE CONTRACTOR AGREES TO PAY ALL FINES AND COSTS INCURRED BY THE OWNER INCLUDING ALL LEGAL COSTS IN THE DEFENSE OF THE OWNER.

401 S. WASHINGTON SQUARE

TEVEN CHRISTENSEN COUNTY DRAIN COMMISSIONEI LAKE BLUFFS DRAIN OF SECTION 14, SOLON TWP, V, LEELANAU COUNTY, MICHIGAN PART C R12W, A I [28N,

Ś

Щ

SC

Attention: If this scale bar does not measure 1" then drawing is not original scale

RELEASE # DATE DESCRIPTION 6/9/2022 11/18/2022 MODIFIED FOR NOV. 2022 RE-BID

esigned By: LCM Checked By: MFS Drawn By: BSF

GEI PROJECT: 2003322 DWG. NO.

01-G-03

SHEET #3

ADDITIONAL FASEMENT INFORMATION

SOIL TYPE LEGEND

SYMBOL

EM

LID

PRIVATE ROAD AUTHORIZATION OVER 66' PRIVATE PLATTED ROW:

*DOCUMENT NO. ON FASEMENT NOTES REFERS TO THE RECORDED DOCUMENT NUMBER FOR THE LEFT ANALL COUNTY REGISTER OF DEEDS

SOIL DESCRIPTION


EDWARDS MUCK-MARL BEDS COMPLEX


KALKASKA-EAST LAKE LOAMY SANDS, 0 TO 6 PERCENT SLOPES, LAKE


MODERATED


LEELANAU-EAST LAKE LOAMY SANDS, 12 TO 18 PERCENT SLOPES


LAKE MODERATED























ADS, Inc. Drainage Handbook Specifications ◆ 1-37

ADS FLARED END SECTION SPECIFICATION


This specification describes 12- through 36-inch (300 to 900mm) ADS Flared End Sections for use in culvert


The ADS Flared End Section shall be high density polyethylene meeting ASTM D3350 minimum cell classification 213320C; contact manufacturer for additional cell classification information. When provided, the metal threaded fastening rod shall be stainless steel.

Installation
Installation shall be in accordance with ADS installation instructions and with those issued by state or local authorities. Contact your local ADS representative or visit www.ads-pipe.com for the latest installation

		PIPE DIAMETER, in (mm)					
Diameter	12	15	18	24	30	36	
in (mm)	(300)	(375)	(450)	(600)	(750)	(900)	
A	6.5	6.5	7.5	7.5	7.5	7.5	
in (mm)	(165)	(165)	(191)	(191)	(191)	(191)	
B (max)	10.0	10.0	15.0	18.0	22.0	25.0	
in (mm)	(254)	(254)	(381)	(475)	(559)	(635)	
Н	6.5	6.5	6.5	6.5	8.6	8.6	
in (mm)	(165)	(165)	(165)	(165)	(218)	(218)	
L	25.0	25.0	32.0	36.0	58.0	58.0	
in (mm)	(635)	(635)	(813)	(914)	(1473)	(1473	
w	29.0	29.0	35.0	45.0	63.0	63.0	
in (mm)	(737)	(737)	(889)	(1143)	(1600)	(1600	









CONCRETE CURB AND GUTTER MDOT TYPE B

CONCRETE CURB AND/OR GUTTER SHALL BE CONSTRUCTED IN ACCORDANCE WITH MDOT STANDARD PLAN R-30-F


STEVEN CHRISTENSEN ELANAU COUNTY DRAIN COMMISSIONER LAKE BLUFFS DRAIN PART OF SECTION 14, SOLON TWP, R12W, LEELANAU COUNTY, MICHIGAN

Щ








NO SCALE



INFILTRATION BASIN DETAIL NO SCALE









*NOTE: WHEN USED IN SERIES. THE TOE OF THE UPSTREAM CHECK DAM SHOULD BE SET AT THE SAME ELEVATION AS THE LOWEST POINT IN THE TOP OF THE DOWNSTREAM CHECK DAM OR AS DIRECTED BY ENGINEER.

Attention If this scale bar does not measure 1" then drawing is RELEASE # DATE 11/18/2022 MODIFIED FOR NOV. 2022 RE-BID esigned By: LCM Checked By: MFS Drawn By: BSF

GEI PROJECT: 2003322


DWG. NO.

99-D-03

SHEET #11

200 Series Installation Detail

ASTM LOAD Class E Concrete Encasement



SECTION

SPECIFICATIONS FILCOTEN PRO-V NW200 - LOAD CLASS E

GENERAL
THE SURFACE DRAINAGE SYSTEM SHALL BE FILCOTEN FIBER COMPOSITE NW100 CHANNEL SYSTEM WITH CONCRETED EDGE MADE OF GALVANIZED STEEL RAILS AS MANUFACTURED BY BG GRASPOINTNER, INC AND DISTRIBUTED BY HYDRO BG USA INC., A WHOLLY OWNED SUBSIDIARY.

MATERIALS

CHANNELS SHALL BE MANUFACTURED FROM FILCOTEN FIBER COMPOSITE WITH CONCRETED EDGE GALVANIZED STEEL RAIL. MINIMUM PROPERTIES OF FILCOTEN FIBER COMPOSITE WILL BE AS FOLLOW

COMPRESSIVE STRENGTH:	11,700
FLEXURAL STRENGTH:	1,700
FREE OF RELEASE AGENTS:	YES
WATER ABSORPTION SUFFICIENT FOR ADHESION WITH CONCRETE SURFACES:	YES
NON FLAMMABLE:	YES
U/V RESISTANT:	YES
RECYCLABLE 100%:	YES
DILUTE ACID AND ALKALI RESISTANT:	YES
FROST THAW SALT TESTED AS PER EN1433 WITH A TEST TEMPERATURE UP TO -40°C (-40°F):	YES
MATERIAL FREE OF VOC. BIOCIDES, HEAVY METALS:	YES


THE SYSTEM SHALL BE 8" (200MM) NOMINAL INTERNAL WIDTH WITH 10.43" UP TO 14.37" (265MM UP TO 365MM). OVERALL WIDTH AND A BUILD-IN SLOPE OF 0.5% AND STEPPED SLOPE SYSTEM, ALL CHANNELS ARE EQUIPPED WITH INTERLOCKING CONNECTION MALE/FEMALE AND SEALANT JOINT

CHANNEL SHALL WITHSTAND LOADING TO PROPER LOAD CLASS AS OUTLINED BY EN 1433. GRATE TYPE SHALL BE APPROPRIATE TO MEET THE SYSTEM LOAD CLASS SPECIFIED AND INTENDED APPLICATION. GRATES SHALL BE SECURED USING 4-POINT BOLTING LOCKING SYSTEM. CHANNEL AND GRATE SHALL BE CERTIFIED TO MEET THE SPECIFIED EN 1433 LOAD CLASS. THE SYSTEM SHALL BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS AND RECOMMENDATIONS.

NOTES:

- INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
- 2. DO NOT SCALE DRAWING
- 3. THIS DRAWING IS INTENDED FOR USE BY ARCHITECTS, ENGINEERS, CONTRACTORS, CONSULTANTS AND DESIGN PROFESSIONALS FOR PLANNING PURPOSES ONLY.
- 4. ALL INFORMATION CONTAINED HEREIN WAS CURRENT AT THE TIME OF DEVELOPMENT BUT MUST BE REVIEWED AND APPROVED BY THE PRODUCT MANUFACTURER TO BE CONSIDERED ACCURATE.





LAKE BLUFFS DRAIN PART OF SECTION 14, SOLON TWP, R12W, LEELANAU COUNTY, MICHIGAN